

TECHNICAL EVALUATION REPORT (SUMMARY)

1. Name of Procuring Agency: University of Health Sciences Lahore
2. Method of Procurement: Single Stage two Envelopes
3. Title of Procurement: Procurement of Laboratory Research Equipment & Work For establishment of Bio Safety Level II Facility at Jinnah Campus Kala Shah Kaku
4. Tender Inquiry No: UHS/Pur/2020
5. Date & Time of Bid Closing: 02-06-2020 at 11:00 AM
6. Date & Time of Bid Opening: 02-06-2020 at 11:30 AM
7. Nos. of Bids Received: 01

Sr. No	Item	Specifications	Vendor participated	
			Midas Inter.	
1	12 HP HVASC	12 HP HVAS unit with DX coil capacity Static Pressure 2" having 2500-2600 CFM Double skin complete in all respect with heating coil, blow, motor, shafts bearing, mixing box, filters chamber. above unit matching with circuit condensing unit along with electrical components, operation and safeties. With approx. 10 RFT copper piping, insulation, control wiring, evacuation pressure testing, gas charging and unit balancing with GI Duct 24/22 swg as per site requirement with Hanger, Bracket, clothing and Glue coating for more protection. HVAC Operation based on HM Programmable Controller.	Quoted as per BOQ	Qualified
2	Supply and installation of terminal (HEPA) filters	Supply and installation of terminal (HEPA) filters box size as per drawing and site	Quoted as per BOQ	Qualified
3	Supply and installation of air terminals Grills and diffusers	Supply and installation of air terminals Grills and diffusers (Size 26" x 26" x & 14" x 14"	Quoted as per BOQ	Qualified
4	Supply and installation of pre bags and Hepa filters	Supply and installation of pre bags and Hepa filters (24" x 24" ,12X12 Bag & Pre-filters	Quoted as per BOQ	Qualified
5	Pass Boxes Size HEPA 24" x 36" (01 Units) + Pass Box with UV/Flourecent Light	Pass Boxes Size HEPA 24" x 36" (01 Units) + Pass Box with UV/Fluorescent Light	Quoted as per BOQ	Qualified
6	Magnehelic Gauges Dwyer USA	Gauges Dwyer USA	Quoted as per BOQ	Qualified
7	SS 304 Paneling with Framing alongwith SS Doors, Windows Double Glazed for BSL-2 Lab and adjacent areas.	SS 304 Paneling with Framing alongwith SS Doors, Windows Double Glazed for BSL-2 Lab and adjacent areas.	Quoted as per BOQ	Qualified
8	Gypsum Ceiling with SMD lights to meet the required Lux with Internal wiring.	Gypsum Ceiling with SMD lights to meet the required Lux with Internal wiring.	Quoted as per BOQ	Qualified
9	Supply and Self Leveling upto 3mm on Floor and Coating on Walls.	Supply and Self Leveling upto 3mm on Floor and Coating on Walls.	Quoted as per BOQ	Qualified


All technical bids were evaluated against the laid specifications and comparative statement (summary/detail) is being submitted to Chairman Tender Committee and Incharge Purchase Cell for further necessary action.

No Complaint Shall be entertained after 03 days of display of Technical Evaluation report.


()



Mr. M. Atif(Director Media & Publication)
Chairman, Tender Committee



Dr. Allah Rakha
HOD Forensic Sciences



Prof. Dr. Shagufta Khalig
Incharge, Purchase Cell